### **X9006 – KNOX-BOX**

## **DESCRIPTION**

# X-1.1 General

**a.** This work shall consist of furnishing and installing knox-box and welded plate as detailed on drawings. This work shall be installed at locations in accordance with the dimensions, design, and details shown in the Contract Documents.

# **EQUIPMENT AND MATERIALS**

## X-2.1 General

- **a.** Knox-box shall be manufactured by Knox-box or equal.
- b. Knox-box shall be 3200 series.
- **c.** Knox box shall be installed on existing metal plate at gates designated on the Contract Documents or on new metal plate at each gates designated on the Contract Documents.
- **d.** All gates without existing metal plates shall have metal plate welded between existing bollards. The work shall be done in accordance with the dimensions, design, and details shown in the Contract Documents.

## **CONSTRUCTION METHODS**

**X-3.1 General.** Furnish, install, and connect all equipment, materials, and incidentals necessary to place the knox-box and welded plate, in operation as a complete unit.