

LATE SEASON STABILIZATION

Jim Rose – Senior Conservation Specialist
Waukesha County Land Resources Division

Spring 2014 Storm Water Workshop

Objective:

- ▣ Stabilize the site with 70% vegetative coverage of all disturbed areas before the end of the growing season.

Deadline #1

- ▣ September 15th
 - Seed & mulch all disturbed areas with permanent seed mix.
 - Regular seeding

If this deadline is missed...

Deadline #2

- ▣ September 15th - October 15th
 - Seed & mulch all disturbed areas with temporary seed mix (oats, winter wheat, annual rye).
 - Permanent seeding must be implemented by June 1st of the following year.

If this deadline is missed...

Deadline #3

- ▣ October 15th - November 1st
 - Two options:
 1. Apply topsoil, seed and the material called for in the approved stabilization plans, where topsoil, seed and erosion matting are called for.
 2. Apply topsoil, seed and Type A Soil Stabilizer from the WDOT Product Acceptability List (PAL) or *other method approved by the LRD* for all areas where topsoil, seed and mulch is called for in the approved plans.

If this deadline is missed...

Deadline #4

- ▣ After November 1st
 - If LRD staff has determined that it is no longer feasible to re-apply topsoil, the permit applicant shall:
 1. Apply Type A Soil Stabilizer from the PAL list to all disturbed areas.
 2. Install ditch checks in all ditches w/slope >0.5% at intervals where the top of the downhill ditch check is at the elevation of the foot of the uphill ditch check.
 - i. Triangular foam-core
 - ii. Stone installed per WDNR Technical Standard
 - iii. Compost-filled tubes, or
 - iv. A comparable product approved by the LRD staff

If this deadline is missed???

Enforcement

Questions???