

Project Summary – January 5, 2026

**CTH YY (Pilgrim Road)
Underwood Creek Structure
Waukesha County
Project I.D. 18-2782(16)**

Project Overview

The proposed project is the replacement of the CTH YY (Pilgrim Road) structure over Underwood Creek in the City of Brookfield. The structure is located approximately 0.25 miles north of CTH M (North Avenue), adjacent to Wirth Park.

The project scope includes replacing the structure at its existing location with a concrete slab bridge. The creek will remain at its existing location. The roadway will remain a two-lane facility and shoulders will be widened to 6-feet. The roadway centerline will be shifted westerly to allow for the shoulder widening. The project limits along CTH YY extend from 150 feet south of Fieldstone Drive to just south of Esser Court. The project includes repairs to existing retaining walls, pavement reconstruction, ditch grading, and guardrail replacement.

Some land acquisition along the west side of CTH YY was required for the project. Utility relocation has been completed. CTH YY (Pilgrim Road) will be closed to traffic for the duration of the construction project. A detour will be posted that follows CTH M (North Avenue) to Calhoun Road to STH 190 (Capitol Drive). Construction of the project is county & state funded.

The current project scope replaces a previous design alternative that proposed relocating Underwood Creek westerly into Wirth Park and shifting the bridge location farther north. That design alternative was abandoned due to cost considerations.

Anticipated Schedule

Utility relocation – October-December 2025

Construction – January 12, 2026 - May 22, 2026

Project Contacts

Kevin Yanny, P.E.
Project Manager
Waukesha County DPW
262-548-7750
kyanny@waukeshacounty.gov

Ethan Moser
Civil Engineer
Waukesha County DPW
262-548-7748
emoser@waukeshacounty.gov

Project Summary – April 16, 2025

**CTH YY (Pilgrim Road)
Underwood Creek Structure
Waukesha County
Project I.D. 18-2782(16)**

Project Overview

The proposed project is the replacement of the CTH YY (Pilgrim Road) structure over Underwood Creek in the City of Brookfield. The structure is located approximately 0.25 miles north of CTH M (North Avenue), adjacent to Wirth Park.

The project scope includes replacing the structure at it's existing location with a concrete slab bridge. The creek will remain at it's existing location. The roadway will remain a two-lane facility and shoulders will be widened to 6-feet. The roadway centerline will be shifted westerly to allow for the shoulder widening. The project limits along CTH YY extend from 150 feet south of Fieldstone Drive to just south of Esser Court. The project includes repairs to existing retaining walls, pavement reconstruction, ditch grading, and guardrail replacement.

Some land acquisition along the west side of CTH YY is required for the project. There is utility relocation that will occur prior to the start of construction. This work will require lane closures , so expect some travel delay. CTH YY (Pilgrim Road) will be closed to traffic for the duration of the construction project. A detour will be posted that follows CTH M (North Avenue) to Calhoun Road to STH 190 (Capital Drive). Construction of the project is county & state funded.

The current project scope replaces a previous design alternative that proposed relocating Underwood Creek westerly into Wirth Park and shifting the bridge location farther north. That design alternative was abandoned due to cost considerations.

.Anticipated Schedule

Utility relocation – April-June, 2025

Construction – Mid-July through fall, 2025.

Project Contacts

Kevin Yanny, P.E
Project Manager
Waukesha County DPW
262-548-7750
kyanny@waukeshacounty.gov

Ethan Moser
Civil Engineer
Waukesha County DPW
262-548-7748
emoser@waukeshacounty.gov