

Project Summary – April 16, 2026

CTH I (Beloit Road)
Bridge over Calhoun Creek B-67-318
Waukesha County
Project I.D. 2722-05-01/71

Project Overview

The existing bridge on CTH I over Calhoun Creek is a three-barrel corrugated steel culvert structure. The bridge is located approximately 0.1 mile west of CTH O (Moorland Road). The culvert barrels are six feet in diameter. The structure was initially constructed in 1976 with two culvert barrels. A third barrel was added in 2009. CTH I (Beloit Road) was reconstructed over the culvert site in 2018. There is significant corrosion of the older steel culvert barrels.

The original project scope was a bridge rehabilitation consisting of structural lining of the culvert barrels. We have changed the scope to a structure replacement. During construction of this project CTH I (Beloit Road) will remain closed to traffic. It is anticipated that acquisition of temporary easements will be necessary to construct/install the culvert liners. The project design and construction will use both federal funds and county funds. Design begun in 2025 and will extend through 2026. Construction is currently scheduled for 2027 but is expected to change.

Anticipated Schedule

Data Gathering and Design – Summer, 2025 - 2026
Public Involvement Meeting – Winter 2026
Real Estate – Spring – Summer 2027
Project LET – April 2027 (Anticipated to Change)
Construction – 2028

Project Contacts

Ethan Moser
Project Manager
Waukesha County
262-548-7746
emoser@waukeshacounty.gov

Dylan Douglas, P.E.
Project Manager
JT Engineering, Inc.
608-204-3304
dyland@jt-engineering.com